

RESOLUTION

CASE NO. SUP-4-06/MP-1-06. PRIME RETAIL MASTER PLAN AMENDMENT

WHEREAS, the Board of Supervisors of James City County has adopted by ordinance specific land uses that shall be subjected to a special use permit (SUP) process; and

WHEREAS, Mr. Greg Davis has applied on behalf of Prime Retail, L.P., for an SUP to allow an expansion of approximately 81,000 square feet on existing and adjacent sites; and

WHEREAS, Mr. Greg Davis has also applied to amend the existing conditions of approval of James City County Case Nos. SUP-25-05 and MP-10-05; and

WHEREAS, the conditions listed below replace and supersede the conditions of approval of James City County Case No. SUP-25-05; and

WHEREAS, the proposed expansion is shown on the master plan prepared by LandMark Design Group, dated May 26, 2006, and entitled "Master Plan Prime Retail Phases I-VIII" and the "Master Plan" and references to phases below refer to phases shown on the master plan;

WHEREAS, the property is located on land zoned B-1, General Business, with proffers that can be further identified as Parcel Nos. (1-28), (1-29), (1-33C), (1-33D), and (1-33E) on James City County Real Estate Tax Map No. (33-3) and on land zoned B-1, General Business, that can be further identified as Parcel No. (1-2) on James City County Real Estate Tax Map. No. (33-3); and

WHEREAS, the Planning Commission of James City County, following its public hearing on June 5, 2006, recommended approval of this application by a vote of 5-1.

NOW, THEREFORE, BE IT RESOLVED that the Board of Supervisors of James City County, Virginia, does hereby approve the issuance of SUP No. 4-06 as described herein with the following conditions:

Conditions Specific to the Phase 5A Expansion

1. Landscaping planters (the type and size of planters to be specified by the landscaping plan) along the entire store frontage of the Phase 5A Expansion as shown on the Master Plan, shall be approved by the Planning Director or his designee prior to final site plan approval for any future expansion. The planters shall be installed prior to issuance of any final Certificate of Occupancy for any future expansion.
2. Applicant has installed a 35-foot-wide transitional buffer planted along the northern most property line adjacent the 5A expansion. This area has been planted and shall be maintained at 133 percent of the numerical standards found in Section 24-94 of the James City County landscape ordinance, and with an emphasis on evergreen shade and understory trees as determined by the Planning Director. The fence already installed in this area shall be a maximum of eight feet high and shall be maintained with a vinyl coating and shall be either black or green in color. Furthermore, the fence shall be maintained with a setback from the property line of at least three feet.

Conditions Specific to the Phase 6 Expansion

1. Prior to final site plan approval for the Phase 6 expansion, the Planning Director shall review and approve the final architectural design of the building(s) prepared as part of the Phase 6 expansion. Such building shall be reasonably consistent, as determined by the Planning Director, with the architectural elevations titled, Prime Outlets Phase 6 expansion, submitted with this SUP application dated, July 6, 2005, and drawn by Gary S. Bowling, Guernsey Tingle Architects.
2. Prior to the issuance of any final Certificate of Occupancy for the Phase 6 expansion, lighting shall be installed for all three entrances from the property onto Richmond Road as shown on the Master Plan. In addition, adequate parking lot lighting shall be installed in the new 43-space parking lot as shown on the Master Plan behind Phase 6 which will be re-stripped from existing parking for buses to parking for cars. The specific location, adequacy, and design of all lighting fixtures shall be approved by the Planning Director. No lighting fixture shall exceed a height of 30 feet.
3. A landscaping plan for the Phase 6 expansion, including foundation landscaping in accordance with James City County Code Section 24, shall be approved by the Planning Director or his designee prior to final site plan approval.
4. Prior to submission of any development plan for the Phase 6 expansion, the applicant shall submit a water and sanitary sewer master plan and hydraulic analyses for the expansion space for review and approval by the James City Service Authority.

Conditions Specific to the Phases 7 and 8 Expansions

1. Prior to any final site plan approval for the Phase 7 and 8 expansions (Building A, B, or C as shown on the master plan), a mass transit plan in accordance with Section 25-59(f) of the James City County Code shall be approved by the Planning Director for Prime Retail. The plan, at a minimum, shall include a replacement bus transfer stop for Williamsburg Area Transit, or its successor, currently located in the Ewell Station shopping center. Installation of all bus stops, shelters and other items approved as part of the mass transit plan shall be completed prior to issuance of any temporary or final Certificate of Occupancy for the Phase 7 and 8 expansions.
2. Prior to any final site plan approval(s) for the Phase 7 and 8 expansions (Building A, B, or C as shown on the master plan), the Planning Director shall review and approve the final architectural design of the building(s) prepared as part of the Phase 7 and 8 expansions, including exterior architectural modifications to the existing Ewell Station Shopping Center. Such building shall be reasonably consistent, as determined by the Planning Director, with the architectural elevations titled, "Prime Outlets Phase 7 and 8 Expansion," submitted with this SUP application dated, February 20, 2006, and drawn by Gary S. Bowling, Guernsey Tingle Architects.
3. Prior to any final site plan approval(s) for the Phase 7 and 8 expansions (Building A, B, or C as shown on the master plan), a landscape plan including foundation landscaping in accordance with James City County Code Chapter 24, shall be approved by the Planning Director or his designee.

4. Landscape waivers are necessary for the approval of parking and stormwater facilities in the Community Character Corridor landscape area along Richmond Road, as shown on the Master Plan. Such waivers shall be subject to the approval of the Development Review Committee.
5. Landscaping shall be installed or bonded, prior to issuance of any temporary or final Certificate of Occupancy for the final building to be constructed (Building A, B, or C as shown on the Master Plan), along the entire Richmond Road frontage of the existing and expanded Prime property that exceeds plant material size requirements in Section 24-90 of the James City County Code by 125%. Such landscaping shall be included on the site plan for the final building to be constructed (Building A, B, or C as shown on the master plan), and subject to approval by the Planning Director.
6. Landscaping shall be installed or bonded prior to any Certificate of Occupancy for the final building to be constructed (Building A, B, or C as shown on the master plan), along the Olde Towne Road frontage that meets current ordinance requirements. Such landscaping shall be included on the site plan for the final building to be constructed, and subject to approval by the Planning Director.
7. Prior to the issuance of any final Certificate of Occupancy for the Phase 7 and 8 expansions (Building A, B, or C as shown on the master plan) lighting shall be installed for the existing entrances from the property onto Olde Towne Road as shown on the Master Plan. The specific location, adequacy, and design of all lighting fixtures shall be approved by the Planning Director. No lighting fixture shall exceed a height of 30 feet.
8. The owner shall be responsible for developing and enforcing water conservation standards to be submitted to and approved by the James City Service Authority prior to any final site plan approval for the Phase 7 and 8 expansions (Building A, B, or C as shown on the master plan). The standards may include, but shall not be limited to such water conservation measures as limitations on the installation and use of irrigation systems and irrigation wells, the use of approved landscaping materials including the use of drought tolerant plants where appropriate, and the use of water conserving fixtures and appliances to promote the intent of this condition which is to conserve water and minimize the use of public water resources to the greatest extent possible.
9. Approved site plans for the Phase 7 and 8 expansions shall reflect the following stormwater management facility improvements:
 - a. PC-186 (located along Olde Towne Road): Infiltration capacity shall be added in accordance with approved James City County Site Plan 110-02, or equivalent measures provided as approved by the Environmental Director;
 - b. PC-124 (located along Olde Towne Road): Shall be retrofitted to improve water quality in accordance with approved James City County Site Plan 110-02, or equivalent measures provided as approved by the Environmental Director;
 - c. PC-036 (behind the existing Food Lion): Shall be retrofitted to incorporate water quality treatment as approved by the Environmental Director; and
 - d. Pre-treatment measures shall be incorporated into development plans as approved by the Environmental Director.

The sequence of construction shall be approved by the Environmental Director, but under no circumstances shall the aforementioned stormwater facilities be completed later than the first Certificate of Occupancy being issued for the final building to be constructed as part of the Phases 7 and 8 expansions (Building A, B, or C as shown on the master plan).

10. Stormwater facility PC-055 (along Richmond Road) shall be modified to incorporate water quality and increased water quantity control as approved by the Environmental Director as part of the site plan for the first building to be constructed (Building A, B, or C as shown on the master plan).
11. The existing stormwater management facilities PC-066 and PC-036 serving the property, subject to the limitations hereinafter provided, shall be reconstructed to permit ground level parking of approximately 237 spaces co-located in, atop and around such facility, as generally depicted on the Master Plan. The reconstruction of PC-066 shall be reflected on the site plan and completed prior to issuance of any Certificate of Occupancy for the first building to be constructed (Building A, B, or C as shown on the master plan). The site plan for the first building to be constructed shall also reflect the reconstruction of PC-036; however, the completion date of PC-036 shall be approved by the Environmental Director, but under no circumstances shall said reconstruction be completed later than the first Certificate of Occupancy being issued for the final phase of expansion (either Building A, B, or C as shown on the master plan). Reconstruction shall be in accordance with all applicable stormwater management ordinances and regulations, and subject to approval by the Environmental Director. Specifically, PC-066 shall be modified to meet the current County requirements for both water quality and channel protection, and PC-036 shall be modified to incorporate water quality protection. The parking reconstruction shall be implemented unless the Environmental Director determines that it cannot be achieved (a) due to engineering constraints, (b) due to environmental, stormwater management or other regulations, ordinances or laws, or (c) that the reconstruction cannot be achieved using soil-covered RainTank (R) devices and Eco-Stone Pavers or equivalent underground stormwater storage units and pervious cover approved by the Environmental Director.

In the event the parking reconstruction is not implemented as described above, the Applicant shall perform and submit a Parking Study, the methodology and parameters of which are subject to approval of the Planning Director. Said study shall be approved by the Board of Supervisors, upon recommendation of the Planning Commission, prior to final site plan approval for the last two buildings to be constructed (Building A, B, or C as shown on the master plan). Specific elements of the study shall include: the identification of the existing parking inventory for Prime Outlets at the time of analysis, the occupancy rate of parking inventory for Prime Outlets for identified periods of analysis, an employee parking analysis, and improvement recommendations. Said site plans shall incorporate approved improvement recommendations.

12. The following road improvements were identified in the "Prime Outlets Phases 7 & 8 Traffic Impact Study" prepared by LandMark Design Group and submitted in February 2006 and revised in June 2006. These improvements are submitted to approval by VDOT and the Planning Director, and shall be made prior to the issuance of any Certificate of Occupancy for any of the proposed additional buildings in the Phase 7 & 8 expansions (Building A, B, or C as shown on the master plan):

- a. Install dual exclusive left-turn lanes with 250 feet of storage and 200-foot tapers on westbound Richmond Road at Olde Towne Road.
 - b. Widen southbound section of Olde Towne Road from Richmond Road to first shopping center entrance ("Bowling Alley entrance") to two full-width lanes, creating two receiving lanes for the dual left-turn lanes referenced in condition (a) above. The outside lane will be a right-turn "drop" lane and the inside lane will serve as a through travel lane.
 - c. Install an exclusive left-turn lane with 200 feet of storage and 200-foot-taper on eastbound Richmond Road at Olde Towne Road to accommodate U-turn movement from eastbound Richmond Road to westbound Richmond Road. Install necessary traffic signal equipment to accommodate the U-turn movement with a protected left-turn phase at the intersection, and install appropriate signage, subject to VDOT approval.
 - d. Modify traffic signal timings and necessary traffic signal equipment at the Richmond Road/Olde Towne Road intersection to accommodate proposed lane configurations and identified new traffic movements.
 - e. Modify traffic signal timings along the Richmond Road corridor to optimize the coordinated system from Airport Road to the western signalized entrance to the property.
 - f. Remove sections of asphalt or otherwise modify the existing continuous right-turn lane on eastbound Richmond Road, subject to approval by VDOT and the Planning Director.
13. A Signal Warrant Analysis for the Olde Towne Road/shopping center entrances must be submitted for approval by VDOT and the Planning Director within 18 months of issuance of the demolition permit for the vehicular access through the existing Phase I building, and prior to final site plan approval for the last two buildings to be constructed (Buildings A, B, or C as shown on the master plan). A second Signal Warrant Analysis must be submitted for approval by VDOT and the Planning Director six months after issuance of the final Certificate of Occupancy for the final phase of expansion (Building A, B, or C as shown on the master plan). In the event a single site plan is submitted and approved for the entire expansion, one Signal Warrant Analysis must be submitted for approval by VDOT and the Planning Director six months after issuance of the final Certificate of Occupancy for the final phase of expansion (Building A, B, or C as shown on the master plan). The analyses shall satisfy VDOT Standard Signal Warrant Analysis requirements, subject to approval by VDOT and the Planning Director. Should traffic signal warrants be met, Applicant shall provide traffic signal(s), and necessary traffic signal equipment (including that associated with cross-coordination of traffic signals) at the Olde Towne Road shopping center entrance(s) in a manner acceptable to VDOT and the Planning Director. Furthermore, Applicant shall provide signal timing plans (AM, Mid-Day, PM, seasonal peak period, Saturday Mid-Day) such that the potential traffic signal(s) shall be coordinated with the Richmond Road/Olde Towne Road traffic signal, subject to the approval of VDOT and the Planning Director. Applicant shall also provide traffic signal timing plans (AM, Mid-Day, PM, seasonal peak period, Saturday Mid-Day) for the identified Richmond Road study area traffic signals to best optimize traffic progression, subject to approval of VDOT and the Planning Director. Such signal(s) and coordination improvements shall be guaranteed by surety prior to issuance of the building permit for the final phase of expansion (either Building B or Building C, as shown on the Master Plan).


14. Upon completion of the first building to be constructed (Building A, B, or C as shown on the master plan), and the vehicular access through the existing Phase I, and the parking area behind the adjacent hotel, as shown on the Master Plan, Applicant shall provide an evaluation of potential access driveway closures or implementable access management strategies along Richmond Road and Olde Towne Road. Said evaluation shall be subject to the approval of VDOT, the Planning Director, and the Development Review Committee prior to site plan approval for the final phase of expansion (Building A, B, or C as shown on the master plan). Such improvements shall be guaranteed by surety prior to issuance of a building permit for the final phase, as described above.
15. Approval of this SUP shall not invalidate the Ewell Station shopping center Phase 2 site plan titled "SP-110-02." SP-110-02 shall be invalidated when construction is commenced pursuant to any site plan associated with this SUP. Construction shall be defined as obtaining permits for building construction and footings and/or foundation has passed required inspections.

Conditions Applicable to all Phases of Prime Retail

1. This SUP shall be valid for the approximately 81,000-square-foot expansion of Prime Retail Phases 7 and 8. The total gross building area shall not exceed 518,264 sq. ft. as shown on Master Plan Titled "Prime Retail Phases I-VIII" dated June 21, 2006, and prepared by LandMark Design Group (The "Master Plan").
2. Development of the site shall be generally in accordance with the above-referenced Master Plan and any questions as to compliance shall be determined by the Development Review Committee (DRC). Minor changes may be permitted by the DRC, as long as they do not change the basic concept or character of the development. This SUP and these conditions shall supersede the existing conditions of approval of James City County Case No. SUP-25-05 and prior SUP conditions affecting the Prime Retail development.
3. Any new exterior site lighting shall be limited to fixtures which are horizontally mounted on light poles not to exceed 30 feet in height and/or other structures and shall be recessed fixtures with no bulb, lens, or globe extending below the casing. The casing shall be opaque and shall completely surround the entire light fixture and light source in such a manner that all light will be directed downward and the light source is not visible from the side. No glare, defined as 0.1 footcandle or higher, shall extend outside the property lines (with the exception of entrance lighting required herein). The use of temporary flood lighting shall be prohibited unless written approval is obtained by the Planning Director for use during a special event.
4. Prior to any final site plan approval for future expansion, all new and existing dumpsters shall be (a) in locations approved by the Planning Director, and (b) screened by landscaping or fencing as approved by the Planning Director.
5. Prior to issuance of any Certificate of Occupancy for any expansion, the applicant shall complete the following: (1) internal driveways shall be designated as "One Way" traffic only, where applicable; (2) fire lane shall be properly marked in accordance with the Virginia Fire Code; and (3) the applicant shall install signage for the rear parking lots and service drives clearly indicating the existence of additional parking spaces for customers and employees. Prior to installation of any new signage,

the applicant shall prepare and submit a comprehensive signage plan for review and approval by the Planning Director.

- 6. If construction has not commenced on this project within 36 months from the issuance of this SUP, the SUP shall become void. Construction shall be defined as obtaining permits for building construction and footings and/or foundation has passed required inspections.
- 7. This SUP is not severable. Invalidation of any word, phrase, clause, sentence or paragraph shall invalidate the remainder.



Bruce C. Goodson
Chairman, Board of Supervisors

ATTEST:



Sanford B. Wanner
Clerk to the Board

<u>SUPERVISOR</u>	<u>VOTE</u>
HARRISON	AYE
ICENHOUR	NAY
MCGLENNON	AYE
BRADSHAW	AYE
GOODSON	AYE

Adopted by the Board of Supervisors of James City County, Virginia, this 27th day of June, 2006.

sup-4-06.res